


**ISOMETRIC IFC - CHECK LIST**

Line Number	021403WWG0005	Stress CN / Level	Nº -	Level: I	<b>TechnipFMC – Butterfly Project</b>			
Isometric Number	023A1021403WWG0005_01	Process Approval Required	YES <input type="checkbox"/>	NO <input checked="" type="checkbox"/>				
		Intrumentation Approval Required (N/A)	YES <input checked="" type="checkbox"/>	NO <input type="checkbox"/>				
<b>Information to be attached:</b>								
Master Copy of PID:	YES <input checked="" type="checkbox"/>	N/A <input type="checkbox"/>	Nº	800124-024-PID-0021-008	Rev. 1			
PID Modification Sheet:	YES <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	Nº		Rev.			
Equipment Vendor Dwg. :	YES <input checked="" type="checkbox"/>	N/A <input type="checkbox"/>	Nº		Rev.			
Instrument Dwg. :	YES <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	Nº		Rev.			
Project By-Pass <sup>(4)</sup> :	YES <input checked="" type="checkbox"/>	N/A <input type="checkbox"/>	Nº	Pendiente por By-Pass	Rev.			
SPO Approved Isometric:	YES <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	Rev.		Extraction Date:			
SIT Approved Isometric:	YES <input type="checkbox"/>	N/A <input checked="" type="checkbox"/>	Rev.		Extraction Date:			
<b>A VERIFICAR / TO BE CHECKED</b> <i>Revision By : (D) Designer / (LDG) Design Leader / (ST) Stress Specialist / (LST) Stress Leader / (SP) Supports Specialist / (LSP) Supports leader / (M) Materials / (SL) Spooler / (CHK) Issuer / (L) Discipline Lead</i>						" N/A " NO APPLICA / NOT APPLICABLE		
Revision By : (D) Designer / (LDG) Design Leader								
Iso Information	Nº de línea según PID y lista de líneas / Line Nbr. according to PID and line list							
	Datos de la línea según lista de líneas / Line data according to line list							
Equipment	Clase de tubería según PID y Lista de Líneas / Piping class according to PID and Line List							
	Vinculo E3D con Diagramas (Process Unit, Temp Operación, Numeracion TODAS válvulas manuales) / Link between E3D and Diagrams (Process Unit, Op Temp, ALL manual valves Tagged)							
Line Design	Diámetro de la línea indicado en número de línea en el cajetín / Line diameter indicated in the line number in the title block							
	Equipo modelado según plano Vendor válido para generar isométrica IFC / Equipment modelled according Vendor drawing valid for Isometric IFC generation Código / Code: 2 <input checked="" type="checkbox"/> 3 <input type="checkbox"/>							
Stress	Nombre de tubuladuras según PID y plano Vendor / Name of nozzle according to PID and Vendor drawing							
	Rating y diámetro de tubuladuras según plano Vendor / Rating and diameter of nozzles according to vendor drawing							
Supports	Posición y elevación de tubuladuras según plano Vendor / Position and elevation of nozzles according to Vendor drawing							
	Revision By : (D) Designer / (LDG) Design Leader							
Materials	Línea sin colisión (verificación incluyendo la nube de puntos) / Line is clash free (checked including points cloud)							
	Comentarios de SPO a líneas críticas recibidos e implementados antes de extracción final para emisión / Process comments to critical lines received and implemented before final extraction for issuance							
Final Check	Verificación contra P&ID y Lista de Lineas / Check Iso vs P&ID and Line List : Correcta referencia de la continuidad de la isométrica en líneas nuevas, líneas existentes u otra hoja de la isométrica en los extremos de línea y sus ramales, incluyendo elevaciones y coordenadas / Correct continuity isometric reference to new lines, existing lines or other isometric sheet in each end of the line and its branches including elevations and coordinates							
	Verificación contra P&ID / Check Iso vs P&ID : Elementos en línea incluidos, secuencia de picajes, pendiente, sentido de flujo, numeración de instrumentos, cambios de especificación, cumplimiento de notas / in-line components included, branch sequence, slope, flow direction, instrument numbering, pipe class breaks, notes accomplishment							
Signature	Verificación contra P&ID / Check Iso vs P&ID : Longitudes requeridas de entrada y/o salida a equipos, distancias y/o elevaciones mínimas o máximas requeridas, formación de condensados / Required inlet and/or outlet lengths to equipments, minimum or maximum distances and/or elevations, condensate generation							
	Comentarios de SIT a recibidos e implementados antes de extracción final para emisión / Instrumentation comments received and implemented before final extraction for issuance							
Final Check	Verificación contra Planos de Vendor o Hook-up Instrumentacion / Check Iso vs Instrument Vendor Drawings or Hook-up : Tamaño de las válvulas de control y de seguridad, instalación de acuerdo a hook-up / Size of control valves and safety valves, instrument installation according to hook-up							
	Picajes según tabla de picajes correspondiente / Branch configuration according to correspondent branch table							
Final Check	Venteos y drenajes de Procesos según requerimientos de PIDs y de puntos altos y bajos para prueba hidrostática y modelados según "assembly" correspondiente / Process vents and drains according PID requirements and high and low points for hydrostatic test and modelled according proper assembly							
	Verificación de distancia mínima entre soldaduras / Check minimum distance between welds							
Final Check	Notas explicativas adicionales incorporadas / Additional clarification notes added							
	Revision By : (ST) Stress Specialist / (LST) Stress Leader							
Final Check	El cálculo de stress disponible no está pendiente de revisión en curso / Available stress calculation is not awaiting for revision							
	Los requisitos según el cálculo de stress están incorporados (si son aplicables) / Stress calculation requirements have been added (if applicable)							
Final Check	Revision By : (SP) Supports Specialist / (LSP) Supports leader							
	La línea está soportada por completo y la lista de soportes está actualizada en el excel extraído del E3D / Line is completely supported and support list updated according file from E3D							
Final Check	Concepto de soporte y separación máxima entre soportes / Support concept and support spans							
	Requerimientos de soportes están de acuerdo al cálculo de stress y ajustados con el especialista de Stress / Support requirements according to stress calculation note are included and adjusted jointly with stress specialist							
Final Check	Numeración correcta de los soportes / Supports correctly numbered							
	Código de soportes correctamente indicados (STD - SPC - COM - MRS - PRF) / Support code correctly indicated (STD - SPC - COM - MRS - PRF)							
Final Check	Marcado de elementos soldados de los soportes en Iso Spool preliminar correspondiente / Mark-up of welded supports components in the correspondent preliminary Iso Spool					N/A		
	Revision By : (M) Materials							
Final Check	La Linea pertenece a alguna o varias categorías de Criticidad. La Linea está listada en la Lista de Lineas Críticas de Materiales. Sus isometrías requieren Verificación exhaustiva / The Line belongs to some or several categories of Criticality. The Line is listed in the Critical Material Lines List. The isometrics require exhaustive verification					N/A		
	Todos los materiales están identificados en la isométrica y se encuentran listados en el listado de materiales / All materials are identified in the isometric and are listed in the BOM							
Final Check	Añadidos elementos especiales de tubería en Línea de acuerdo a PIDs última revisión y lista de especiales de tubería (Verificar en adicional correcta Numeración, criterios de Posicionamiento en diseño si aplican) / Inclusion of special piping elements in line according to PIDs latest review and Special Piping Material List (Verify identification number, piping design location criteria if applicable)					N/A		
	Nº de identificación de válvulas manuales (según PID) / Identification number of manual valve (according to PID)							
Final Check	Todas las juntas y pernos colocadas según tipo requerido (RF, FF, Bolts, Machine Bolts) / All gaskets and bolts placed according required type (RF, FF, Bolts, Machine Bolts)							
	Extensión de volante de válvula modelada y reflejada en lista de materiales de la isométrica / Valves axis extension modelled and reflected in Isometric BOM					N/A		
Final Check	Válvulas colocadas según PID y Piping Class / Valves placed according PID an Piping Class							
	Revision By : (CHK) Issuer							
Final Check	La isométrica verificada por Procesos (SPO) se corresponde a la última revisión / The isometric verified by Process (SPO) corresponds to its last revision							
	La isométrica verificada por Instrumentación (SIT) se corresponde a la última revisión / The isometric verified by Instrumentation (SIT) corresponds to its last revision							
Final Check	Las notas a mano están incorporadas en las isométricas / The hand-made annotation is included							
	La revisión de los documentos para la verificación siguen siendo las actuales / Current revision of documents for checking are still the latest available							
Final Check	El número de revisión y la fecha son correctos / The revision number and the date are correct							
	Todos los comentarios se han revisado para ser incluidos o descartados / All comments have been checked to be included or discarded							
Final Check	Holds resueltos o en su defecto By-Pass aprobado / Holds resolved or instead By-Pass approved							
	<b>SIGNATURES (Name and date)</b>							
DESIGN LEADER (LD)	<b>REVIEWED</b> By rvasquezhu at 11:19 am, Dec 16, 2020		<b>REVIEWED</b> By Jose G. Suarez at 12:52 pm, Jan 14, 2021	SUPPORTS LEADER (LSP)	<b>REVIEWED</b> By Sergio Zamora at 7:32 am, Jan 21, 2021		ISSUER (CHK)	<b>REVIEWED</b> By oscar at 8:44 am, Jan 22, 2021
STRESS LEADER (LST)			MATERIALS (M)	<b>REVIEWED</b> By Jose G. Suarez at 4:34 pm, Jan 21, 2021		DISCIPLINE LEAD (L)		

**NOTES:**

- [1] If "X" marqued, a "HOLD" note should be included in the Holds area for justification.  
[2] 1st checking round: Checker to place a (✓) or a (X) confirming or not Designer verification. A (✓) or a (X) should also be placed to confirm or reject any (X) mark placed by the Designer confirming or not the implicit HOLD.  
[3] 2nd checking round: Checker to place a (✓) to validate the points that were not confirmed in the 1st round and were corrected by respective Specialist.  
[4] If an isometric with HOLD is approved by IFC Leader for issuance, the correspondent By-Pass should be attached.



**PIPING DPT.  
ISSUER  
CHECKED**

By oscar at 8:42 am, Jan 22, 2021

0	21/01/21	APN	LPD	OMC	IFC-ISSUED FOR CONSTRUCTION
REV	DATE	DWN	CHK	APP	DESCRIPTION

All dimensions to be checked in field prior to construction. Dimensions and routing shall be field adjusted, it is the piping contractors responsibility to check and verify all closing dimensions to equipment and make adjustments as required in field. All dimensions, elevations and coordinates are in millimeter unless noted otherwise. Fieldwelds and overlengths to be determined by piping contractor. Bolt holes to straddle horizontal and vertical centerline unless shown otherwise. Contractor will provide all necessary pipe supports.

NOTES:

For pipes < dn50 supporting to be studied and defined by construction contractor before line fabrication and installation.

REFERENCES / DOCUMENTS

LINE LIST	30201-042-001000-001
ISOMETRIC INDEX	30303-042-023000-200
PIPING SUPPORT	30207-042-021300-001

SPEC

SYMBOLIC

16SS21

PROJECT DESCRIPTION/LOCATION

BUTTERFLY PROJECT/KREFELD



Insulated Pipe

Insulated and Traced Pipe

— — — — —

PROCESS UNIT

DESIGN AREA


LINE NUMBER

TRAIN

sheet

REV

024 023A1 021403-100-WWG-16SS21-0005 01 1 OF 2 0


**MATERIAL LIST - FABRICATION**

PT NO	N.S. (MM)	DESCRIPTION	IDENT	QTY
1	100	Pipes (Length), EN 10220, BE, EFW + 100% RT, -, /2.6MM EN 10217-7 Gr.X2CrNi19-11,	C1KV25CN	21.6M
2	100 x 40	Half Coup, Prj Std, BSPPF End, 40 Bar, -, -, / EN 10216-5 Gr.X2CrNi19-11,	C3CLV94W	1
3	100	90° Elb LR, EN 10253-4 Type A, BW Ends, Welded + 100% RT, C1P0SBDW M.3D, Serie 2./2.6MM EN 10253-4 Gr.X2CrNi19-11,		8

**MATERIAL LIST - ERECTION**

PT NO	N.S. (MM)	DESCRIPTION	IDENT	QTY
4	40	GENERIC TRANSMITTER SCREWED 021403PT001	- -	1


**PIPING DPT.  
ISSUER  
CHECKED**

By oscar at 8:42 am, Jan 22, 2021

0	21/01/21	APN	LPD	OMC	IFC-ISSUED FOR CONSTRUCTION
REV	DATE	DWN	CHK	APP	DESCRIPTION

ALL dimensions to be checked in field prior to construction. Dimensions and routing shall be field adjusted, it is the piping contractors responsibility to check and verify all closing dimensions to equipment and make adjustments as required in field. All dimensions, elevations and coordinates are in millimeter unless noted otherwise. Fieldwelds and overlengths to be determined by piping contractor. Bolt holes to straddle horizontal and vertical centerline unless shown otherwise. Contractor will provide all necessary pipe supports.

PROCESS UNIT	DESIGN AREA	LINE NUMBER			TRAIN	SHEET	REV
		024	023A1	021403-100-WWG-16SS21-0005			
					01	2 OF 2	0


**MATERIAL LIST - FABRICATION**

PT NO	N.S. (MM)	DESCRIPTION	IDENT	QTY
1	100	Pipes (Length), EN 10220, BE, EFW + 100% RT, -,./2.6MM EN 10217-7 Gr.X2CrNi19-11,	C1KV25CN	1.0M
2	150 x 100	Conc Reducer, EN 10253-4 Type A, BW Ends, Welded + 100% RT, -,./2.6MM/2.6MM EN 10253-4 Gr.X2CrNi19-11,	C1NFELSO	1
3	100 x 100	Eq Te, EN 10253-4 Type A, BW Ends, Welded + 100% RT, -,./2.6MM EN 10253-4 Gr.X2CrNi19-11,	C1MSER99	2
4	100 x 40	Half Coup, Prj Std, BSPPF End, 40 Bar, -, -,./ EN 10216-5 Gr.X2CrNi19-11,	C3CLV94W	1
5	100	45° Elb LR, EN 10253-4 Type A, BW Ends, Welded + 100% RT, C1P0SATW M.3D, Serie 2,./2.6MM EN 10253-4 Gr.X2CrNi19-11,	1	
6	100	90° Elb LR, EN 10253-4 Type A, BW Ends, Welded + 100% RT, C1P0SBDW M.3D, Serie 2,./2.6MM EN 10253-4 Gr.X2CrNi19-11,	2	
7	150	WN Flg, EN 1092-1, RF/BW End, PN 40, -,./4.5MM EN 10222-5 Gr.X2CrNi18-9,	C1MSERA	1
8	100	WN Flg, EN 1092-1, RF/BW End, PN 16, -,./3.6MM EN 10222-5 Gr.X2CrNi18-9,	C1KU0MMW	7

**MATERIAL LIST - ERECTION**

PT NO	N.S. (MM)	DESCRIPTION	IDENT	QTY
9	150	NM Flat Gk, EN 1514-1, RF as per EN 1092-1, PN 16, IBC Type, Thk-3.2mm, Klingsersil C-4430, TA-Luft & EC1935 (D.S. 5101)/ CNAF,	C1NKU6DX	1
10	100	NM Flat Gk, EN 1514-1, RF as per EN 1092-1, PN 16, IBC Type, Thk-3.2mm, Klingsersil C-4430, TA-Luft & EC1935 (D.S. 5101)/ CNAF,	C1NKU6DV	1
11	24	135 SBLT 2 HHx N&2W, ISO 261/ISO 4032, Full Length Threaded, F.Wash. EN ISO 887, A2, EN ISO 7089 ISO 3506-1 Gr.A2-70,	C3JHBD3	8
12	16	160 SBLT 2 HHx N&2W, ISO 261/ISO 4032, Full Length Threaded, F.Wash. EN ISO 887, A2, EN ISO 7089 ISO 3506-1 Gr.A2-70,	C3JHBD8B	24
13	16	100 SBLT 2 HHx N&2W, ISO 261/ISO 4032, Full Length Threaded, F.Wash. EN ISO 887, A2, EN ISO 7089 ISO 3506-1 Gr.A2-70,	C3JHBD7Z	8
14	100	But Waf,PN 16,RF or FF,Datasheet: 6102/ Ductile Iron, GENERIC TRANSMITTER SCREWED 021403PT012	C1UYHNWF	2
15	40	- -	-	1

**PIPING DPT.  
MATERIALS  
CHECKED**

By Jose G. Suarez at 4:34 pm, Jan 21, 2021

0	21/01/21	APN	LPD	OMC	IFC-ISSUED FOR CONSTRUCTION
REV	DATE	DWN	CHK	APP	DESCRIPTION

All dimensions to be checked in field prior to construction. Dimensions and routing shall be field adjusted, it is the piping contractors responsibility to check and verify all closing dimensions to equipment and make adjustments as required in field. All dimensions, elevations and coordinates are in millimeter unless noted otherwise. Fieldwelds and overlengths to be determined by piping contractor. Bolt holes to straddle horizontal and vertical centerline unless shown otherwise. Contractor will provide all necessary pipe supports.

**NOTES:**


For pipes < dn50 supporting to be studied and defined by construction contractor before line fabrication and installation.

**REFERENCES / DOCUMENTS**


LINE LIST	30201-042-001000-001
ISOMETRIC INDEX	30303-042-023000-200
PIPING SUPPORT	30207-042-021300-001

**SPEC**
**SYMBOLIC**

Insulated Pipe	Insulated and Traced Pipe
— — — —	— — — —

**PROJECT DESCRIPTION/LOCATION**
**BUTTERFLY PROJECT/KREFELD**


PROCESS UNIT	DESIGN AREA	LINE NUMBER	TRAIN	sheet	REV
024	023A1	021403-100-WWG-16SS21-0005	01	1 OF 2	0



## MATERIAL LIST – FABRICATION

<u>PT NO</u>	<u>N.S. (MM)</u>	<u>DESCRIPTION</u>	<u>IDENT</u>	<u>QTY</u>
1	100	Pipes (Length), EN 10220, BE, EFW + 100% RT, -, /2.6MM EN 10217-7 Gr.X2CrNi19-11,	C1KV25CN	21.6M
2	100 x 40	Half Coup, Prj Std, BSPPF End, 40 Bar, -, -, / EN 10216-5 Gr.X2CrNi19-11,	C3CLV94W	1
3	100	90° Elb LR, EN 10253-4 Type A, BW Ends, Welded + 100% RT, M.3D, Serie 2, /2.6MM EN 10253-4 Gr.X2CrNi19-11,	C1P0SBDW	8

#### MATERIAL LIST - ERECTION

<u>PT NO</u>	<u>N.S. (MM)</u>	<u>DESCRIPTION</u>	<u>IDENT</u>	<u>QTY</u>	
4	40	GENERIC TRANSMITTER,SCREWED	021403PT001	- -	1


**PIPING DPT.**  
**MATERIALS**  
**CHECKED**

By Jose G. Suarez at 4:34 pm, Jan 21, 2021

0	21/01/21	APN	LPD	OMC	IFC-ISSUED FOR CONSTRUCTION
REV	DATE	DWN	CHK	APP	DESCRIPTION

All dimensions to be checked in field prior to construction. Dimensions and routing shall be field adjusted, it is the piping contractors responsibility to check and verify all closing dimensions to equipment and make adjustments as required in field. All dimensions, elevations and coordinates are in millimeter unless noted otherwise. Fieldwelds and overlengths to be determined by piping contractor. Bolt holes to straddle horizontal and vertical centerline unless shown otherwise. Contractor will provide all necessary pipe supports.

NOTES:		REFERENCES / DOCUMENTS		SPEC	16SS21	PROJECT DESCRIPTION/LOCATION		horizontal and vertical centerline unless shown otherwise. Contractor will provide all necessary pipe supports.		
				SYMBOLS		BUTTERFLY PROJECT/KREFELD				
		LINE LIST	30201-042-001000-001	Insulated Pipe — — — —	Insulated and Traced Pipe — — — —	LINE NUMBER		TRAIN	SHEET	REV
		ISOMETRIC INDEX	30303-042-023000-200							
		PIPING SUPPORT	30207-042-021300-001							
For pipes < dn50 supporting to be studied and defined by construction contractor before line fabrication and installation.										


**MATERIAL LIST - FABRICATION**


PT NO	N.S. (MM)	DESCRIPTION	IDENT	QTY
1	100	Pipes (Length), EN 10220, BE, EFW + 100% RT, -,./2.6MM EN 10217-7 Gr.X2CrNi19-11,	C1KV25CN	1.0M
2	150 x 100	Conc Reducer, EN 10253-4 Type A, BW Ends, Welded + 100% RT, -,./2.6MM/2.6MM EN 10253-4 Gr.X2CrNi19-11,	C1NFELSO	1
3	100 x 100	Eq Te, EN 10253-4 Type A, BW Ends, Welded + 100% RT, -,./2.6MM EN 10253-4 Gr.X2CrNi19-11,	C1MSER99	2
4	100 x 40	Half Coup, Prj Std, BSPPF End, 40 Bar, -, -,./ EN 10216-5 Gr.X2CrNi19-11,	C3CLV94W	1
5	100	45° Elb LR, EN 10253-4 Type A, BW Ends, Welded + 100% RT, C1P0SATW M.3D, Serie 2,./2.6MM EN 10253-4 Gr.X2CrNi19-11,	1	
6	100	90° Elb LR, EN 10253-4 Type A, BW Ends, Welded + 100% RT, C1P0SBDW M.3D, Serie 2,./2.6MM EN 10253-4 Gr.X2CrNi19-11,	2	
7	150	WN Flg, EN 1092-1, RF/BW End, PN 40, -,./4.5MM EN 10222-5 Gr.X2CrNi18-9,	C1MSERA	1
8	100	WN Flg, EN 1092-1, RF/BW End, PN 16, -,./3.6MM EN 10222-5 Gr.X2CrNi18-9,	C1KU0MMW	7

**MATERIAL LIST - ERECTION**

PT NO	N.S. (MM)	DESCRIPTION	IDENT	QTY
9	150	NM Flat Gk, EN 1514-1, RF as per EN 1092-1, PN 16, IBC Type, Thk-3.2mm, Klingsersil C-4430, TA-Luft & EC1935 (D.S. 5101)/ CNAF,	C1NKU6DX	1
10	100	NM Flat Gk, EN 1514-1, RF as per EN 1092-1, PN 16, IBC Type, Thk-3.2mm, Klingsersil C-4430, TA-Luft & EC1935 (D.S. 5101)/ CNAF,	C1NKU6DV	1
11	24	135 SBLT 2 HHx N&2W, ISO 261/ISO 4032, Full Length Threaded, F.Wash. EN ISO 887, A2, EN ISO 7089 ISO 3506-1 Gr.A2-70,	C3JHBD3	8
12	16	160 SBLT 2 HHx N&2W, ISO 261/ISO 4032, Full Length Threaded, F.Wash. EN ISO 887, A2, EN ISO 7089 ISO 3506-1 Gr.A2-70,	C3JHBD8B	24
13	16	100 SBLT 2 HHx N&2W, ISO 261/ISO 4032, Full Length Threaded, F.Wash. EN ISO 887, A2, EN ISO 7089 ISO 3506-1 Gr.A2-70,	C3JHBD7Z	8
14	100	But Waf,PN 16,RF or FF,Datasheet: 6102/ Ductile Iron, GENERIC TRANSMITTER SCREWED 021403PT012	C1UYHNWF	2
15	40	- -	- -	1

ALL dimensions to be checked in field prior to construction. Dimensions and routing shall be field adjusted, it is the piping contractors responsibility to check and verify all closing dimensions to equipment and make adjustments as required in field. All dimensions, elevations and coordinates are in millimeter unless noted otherwise. Fieldwelds and overlengths to be determined by piping contractor. Bolt holes to straddle horizontal and vertical centerline unless shown otherwise. Contractor will provide all necessary pipe supports.

REV	DATE	DWN	CHK	APP	DESCRIPTION
0	21/01/21	APN	LPD	OMC	IFC-ISSUED FOR CONSTRUCTION



## MATERIAL LIST – FABRICATION

<u>PT NO</u>	<u>N.S. (MM)</u>	<u>DESCRIPTION</u>	<u>IDENT</u>	<u>QTY</u>
1	100	Pipes (Length), EN 10220, BE, EFW + 100% RT, - ,/2.6MM EN 10217-7 Gr.X2CrNi19-11,	C1KV25CN	21.6M
2	100 x 40	Half Coup, Prj Std, BSPPF End, 40 Bar, - , - ,/ EN 10216-5 Gr.X2CrNi19-11,	C3CLV94W	1
3	100	90° Elb LR, EN 10253-4 Type A, BW Ends, Welded + 100% RT, M.3D, Serie 2,/2.6MM EN 10253-4 Gr.X2CrNi19-11,	C1P0SBDW	8

#### MATERIAL LIST - ERECTION

<u>PT NO</u>	<u>N.S. (MM)</u>	<u>DESCRIPTION</u>	<u>IDENT</u>	<u>QTY</u>	
4	40	GENERIC TRANSMITTER,SCREWED	021403PT001	- -	1


**PIPING DPT.  
DESIGNED**

By aperezpune at 4:12 pm - Jan 21, 2021

By user name at 4:12 pm, Sun 27, 2021					
REV	DATE	DWN	CHK	APP	DESCRIPTION
0	21/01/21	APN	LPD	OMC	IFC-ISSUED FOR CONSTRUCTION

All dimensions to be checked in field prior to construction. Dimensions and routing shall be field adjusted, it is the piping contractors responsibility to check and verify all closing dimensions to equipment and make adjustments as required in field. All dimensions, elevations and coordinates are in millimeter unless noted otherwise. Fieldwelds and overlengths to be determined by piping contractor. Bolt holes to straddle horizontal and vertical centerline unless shown otherwise. Contractor will provide all necessary pipe supports.

NOTES:		REFERENCES / DOCUMENTS		SPEC	16SS21	PROJECT DESCRIPTION/LOCATION		horizontal and vertical centerline unless shown otherwise. Contractor will provide all necessary pipe supports.		
				SYMBOLS		BUTTERFLY PROJECT/KREFELD				
		LINE LIST	30201-042-001000-001	Insulated Pipe — — — —	Insulated and Traced Pipe — — — — — — — — — —	LINE NUMBER		TRAIN	SHEET	REV
For pipes < dn50 supporting to be studied and defined by construction contractor before line fabrication and installation.		ISOMETRIC INDEX	30303-042-023000-200							
		PIPING SUPPORT	30207-042-021300-001			024 023A1 021403-100-WWG-16SS21-0005		01	2 OF 2	0



## MATERIAL LIST - FABRICATION

PT NO	N.S. (MM)	DESCRIPTION	IDENT	QTY
1	100	Pipes (Length), EN 10220, BE, EFW + 100% RT, -,./2.6MM EN 10217-7 Gr.X2CrNi19-11,	C1KV25CN	1.0M
2	150 x 100	Conc Reducer, EN 10253-4 Type A, BW Ends, Welded + 100% RT, -,./2.6MM/2.6MM EN 10253-4 Gr.X2CrNi19-11,	C1NFELSO	1
3	100 x 100	Eq Te, EN 10253-4 Type A, BW Ends, Welded + 100% RT, -,./2.6MM EN 10253-4 Gr.X2CrNi19-11,	C1MSER99	2
4	100 x 40	Half Coup, Prj Std, BSPPF End, 40 Bar, -, -,./ EN 10216-5 Gr.X2CrNi19-11,	C3CLV94W	1
5	100	45° Elb LR, EN 10253-4 Type A, BW Ends, Welded + 100% RT, C1P0SATW M.3D, Serie 2,./2.6MM EN 10253-4 Gr.X2CrNi19-11,	1	
6	100	90° Elb LR, EN 10253-4 Type A, BW Ends, Welded + 100% RT, C1P0SBDW M.3D, Serie 2,./2.6MM EN 10253-4 Gr.X2CrNi19-11,	2	
7	150	WN Flg, EN 1092-1, RF/BW End, PN 40, -,./4.5MM EN 10222-5 Gr.X2CrNi18-9,	C1MSERA	1
8	100	WN Flg, EN 1092-1, RF/BW End, PN 16, -,./3.6MM EN 10222-5 Gr.X2CrNi18-9,	C1KU0MMW	7

## MATERIAL LIST - ERECTION

PT NO	N.S. (MM)	DESCRIPTION	IDENT	QTY
9	150	NM Flat Gk, EN 1514-1, RF as per EN 1092-1, PN 16, IBC Type, Thk-3.2mm, Klingsersil C-4430, TA-Luft & EC1935 (D.S. 5101)/ CNAF,	C1NKU6DX	1
10	100	NM Flat Gk, EN 1514-1, RF as per EN 1092-1, PN 16, IBC Type, Thk-3.2mm, Klingsersil C-4430, TA-Luft & EC1935 (D.S. 5101)/ CNAF,	C1NKU6DV	1
11	24	135 SBLT 2 HHx N&2W, ISO 261/ISO 4032, Full Length Threaded, F.Wash. EN ISO 887, A2, EN ISO 7089 ISO 3506-1 Gr.A2-70,	C3JHBD3	8
12	16	160 SBLT 2 HHx N&2W, ISO 261/ISO 4032, Full Length Threaded, F.Wash. EN ISO 887, A2, EN ISO 7089 ISO 3506-1 Gr.A2-70,	C3JHBD8B	24
13	16	100 SBLT 2 HHx N&2W, ISO 261/ISO 4032, Full Length Threaded, F.Wash. EN ISO 887, A2, EN ISO 7089 ISO 3506-1 Gr.A2-70,	C3JHBD7Z	8
14	100	But Waf,PN 16,Lug-type RF,Datasheet: 6105/ Ductile Iron,	C1UMDY6C	1
15	100	But Waf,PN 16,RF or FF,Datasheet: 6102/ Ductile Iron,	C1UYHNWF	1
16	40	GENERIC TRANSMITTER SCREWED 021403PT012	- -	1

PIPING DPT.  
**SUPPORTS CHECKED**  
By Sergio Zamora at 7:34 am, Jan 21, 2021

PIPING DPT.  
**SUPPORTED**  
By mfernandez1 at 4:43 pm, Jan 20, 2021

PIPING DPT.  
**DESIGNED**  
By apereznune at 9:23 am, Jan 20, 2021

PIPING DPT.  
**DESIGN CHECKED**  
By oscar at 4:05 pm, Jan 20, 2021

0	20/01/21	APN	LPD	OMC	IFC-ISSUED FOR CONSTRUCTION
REV	DATE	DWN	CHK	APP	DESCRIPTION

All dimensions to be checked in field prior to construction. Dimensions and routing shall be field adjusted, it is the piping contractors responsibility to check and verify all closing dimensions to equipment and make adjustments as required in field. All dimensions, elevations and coordinates are in millimeter unless noted otherwise. Fieldwelds and overlengths to be determined by piping contractor. Bolt holes to straddle horizontal and vertical centerline unless shown otherwise. Contractor will provide all necessary pipe supports.

PROCESS UNIT	DESIGN AREA	LINE NUMBER			TRAIN	SHEET	REV
		024	023A1	021403-100-WWG-16SS21-0005			
					01	1 OF 2	0

## NOTES:

For pipes < dn50 supporting to be studied and defined by construction contractor before line fabrication and installation.



## REFERENCES / DOCUMENTS

LINE LIST	30201-042-001000-001
ISOMETRIC INDEX	30303-042-023000-200
PIPING SUPPORT	30207-042-021300-001

## SPEC


## SYMBOLIC

## 16SS21



## PROJECT DESCRIPTION/LOCATION

## BUTTERFLY PROJECT/KREFELD



## MATERIAL LIST - FABRICATION

<u>PT NO</u>	<u>N.S. (MM)</u>	<u>DESCRIPTION</u>	<u>IDENT</u>	<u>QTY</u>
1	100	Pipes (Length), EN 10220, BE, EFW + 100% RT, - ,/2.6MM EN 10217-7 Gr.X2CrNi19-11,	C1KV25CN	21.6M
2	100 x 40	Half Coup, Prj Std, BSPPF End, 40 Bar, - , - ,/ EN 10216-5 Gr.X2CrNi19-11,	C3CLV94W	1
3	100	90° Elb LR, EN 10253-4 Type A, BW Ends, Welded + 100% RT, M.3D, Serie 2 ,/2.6MM EN 10253-4 Gr.X2CrNi19-11,	C1P0SBDW	8

MATERIAL LIST - ERECTION

<u>PT NO</u>	<u>N.S. (MM)</u>	<u>DESCRIPTION</u>	<u>IDENT</u>	<u>QTY</u>
4	40	GENERIC TRANSMITTER,SCREWED 021403PT001	- -	1

**PIPING DPT.**  
**SUPPORTED**

By mfernandes1 at 4:13 pm - Jan 20, 2021

**PIPING DPT.  
DESIGNED**

Report generated on 10/22/2014 at 10:22:11


**PIPING DPT.**  
**SUPPORTS**  
**CHECKED**

© 2010 Pearson Education, Inc. All Rights Reserved. May not be reproduced without permission.

By appointment at 07:00 am, Sat. 26, 2021					
0	20/01/21	APN	LPD	OMC	IFC-ISSUED FOR CONSTRUCTION
REV	DATE	DWN	CHK	APP	DESCRIPTION


All dimensions to be checked in field prior to construction. Dimensions and routing shall be field adjusted, it is the piping contractors responsibility to check and verify all closing dimensions to equipment and make adjustments as required in field. ALL dimensions, elevations and coordinates are in millimeter unless noted otherwise. Fieldwelds and overlengths to be determined by piping contractor. Bolt holes to straddle horizontal and vertical centerline unless shown otherwise. Contractor will provide all necessary pipe supports.

NOTES:							Horizontal and vertical centerline unless shown otherwise. Contractor will provide all necessary pipe supports.										
REFERENCES / DOCUMENTS							SPEC	16SS21		PROJECT DESCRIPTION/LOCATION							
							SYMBOLS		BUTTERFLY PROJECT/KREFELD			 TechnipFMC					
LINE LIST			30201-042-001000-001				Insulated Pipe		Insulated and Traced Pipe								
ISOMETRIC INDEX			30303-042-023000-200									PROCESS UNIT	DESIGN AREA	LINE NUMBER	TRAIN	SHEET	REV
For pipes < dn50 supporting to be studied and defined by construction contractor before line fabrication and installation.												024	023A1	021403-100-WWG-16SS21-0005	01	2 OF 2	0
PIPING SUPPORT			30207-042-021300-001														



PROJECT DESCRIPTION/LOCATION						LINE NUMBER			TRAIN	SHEET	REV
BUTTERFLY PROJECT/KREFELD						024	023A1	021403-100-WWG-16SS21-0005	01	1 OF 2	0
0	16/12/20	APN	LPD	OMC	IFC-ISSUED FOR CONSTRUCTION						
REV	DATE	DWN	CHK	APP	DESCRIPTION						

ALL dimensions to be checked in field prior to construction. Dimensions and routing shall be field adjusted, it is the piping contractors responsibility to check and verify all closing dimensions to equipment and make adjustments as required in field. All dimensions, elevations and coordinates are in millimeter unless noted otherwise. Fieldwelds and overlengths to be determined by piping contractor. Bolt holes to straddle horizontal and vertical centerline unless shown otherwise. Contractor will provide all necessary pipe supports.


**MATERIAL LIST - FABRICATION**

PT NO	N.S. (MM)	DESCRIPTION	IDENT	QTY
1	100	Pipes (Length), EN 10220, BE, EFW + 100% RT, -, /2.6MM EN 10217-7 Gr.X2CrNi19-11,	C1KV25CN	21.6M
2	100 x 40	Half Coup, Prj Std, BSPPF End, 40 Bar, -, -, / EN 10216-5 Gr.X2CrNi19-11,	C3CLV94W	1
3	100	90° Elb LR, EN 10253-4 Type A, BW Ends, Welded + 100% RT, C1P0SBDW M.3D, Serie 2./2.6MM EN 10253-4 Gr.X2CrNi19-11,	8	

**MATERIAL LIST - ERECTION**

PT NO	N.S. (MM)	DESCRIPTION	IDENT	QTY
4	40	GENERIC TRANSMITTER SCREWED 021403PT001	- -	1

**PIPING DPT.  
MATERIALS  
WITH COMMENTS**

By Jose G. Suarez at 12:58 pm, Jan 14, 2021

0	16/12/20	APN	LPD	OMC	IFC-ISSUED FOR CONSTRUCTION
REV	DATE	DWN	CHK	APP	DESCRIPTION

ALL dimensions to be checked in field prior to construction. Dimensions and routing shall be field adjusted, it is the piping contractors responsibility to check and verify all closing dimensions to equipment and make adjustments as required in field. All dimensions, elevations and coordinates are in millimeter unless noted otherwise. Fieldwelds and overlengths to be determined by piping contractor. Bolt holes to straddle horizontal and vertical centerline unless shown otherwise. Contractor will provide all necessary pipe supports.

**NOTES:**

For pipes < dn50 supporting to be studied and defined by construction contractor before line fabrication and installation.


**REFERENCES / DOCUMENTS**

LINE LIST	30201-042-001000-001
ISOMETRIC INDEX	30303-042-023000-200
PIPING SUPPORT	30207-042-021300-001

**SPEC**
**SYMBOLS**
**16SS21**
**BUTTERFLY PROJECT/KREFELD**

PROCESS UNIT	DESIGN AREA	LINE NUMBER	TRAIN	sheet	REV
024	023A1	021403-100-WWG-16SS21-0005	01	2 OF 2	0




**MATERIAL LIST - FABRICATION**

PT NO	N.S. (MM)	DESCRIPTION	IDENT	QTY
1	100	Pipes (Length), EN 10220, BE, EFW + 100% RT, -,./2.6MM EN 10217-7 Gr.X2CrNi19-11,	C1KV25CN	1.0M
2	150 x 100	Conc Reducer, EN 10253-4 Type A, BW Ends, Welded + 100% RT, -,./2.6MM/2.6MM EN 10253-4 Gr.X2CrNi19-11,	C1NFELSO	1
3	100 x 100	Eq Te, EN 10253-4 Type A, BW Ends, Welded + 100% RT, -,./2.6MM EN 10253-4 Gr.X2CrNi19-11,	C1MSER99	2
4	100 x 40	Half Coup, Prj Std, BSPPF End, 40 Bar, -, -,./ EN 10216-5 Gr.X2CrNi19-11,	C3CLV94W	1
5	100	45° Elb LR, EN 10253-4 Type A, BW Ends, Welded + 100% RT, C1P0SATW M.3D, Serie 2,./2.6MM EN 10253-4 Gr.X2CrNi19-11,	1	
6	100	90° Elb LR, EN 10253-4 Type A, BW Ends, Welded + 100% RT, C1P0SBDW M.3D, Serie 2,./2.6MM EN 10253-4 Gr.X2CrNi19-11,	2	
7	150	WN Flg, EN 1092-1, RF/BW End, PN 40, -,./4.5MM EN 10222-5 Gr.X2CrNi18-9,	C1MSERA	1
8	100	WN Flg, EN 1092-1, RF/BW End, PN 16, -,./3.6MM EN 10222-5 Gr.X2CrNi18-9,	C1KU0MMW	7

**MATERIAL LIST - ERECTION**


PT NO	N.S. (MM)	DESCRIPTION	IDENT	QTY
9	150	NM Flat Gk, EN 1514-1, RF as per EN 1092-1, PN 16, IBC Type, Thk-3mm, Gore-Gr style R, TA-Luft & EC1935 (D.S. 5103) / Modified PTFE,	C1NKU6DJ	1
10	100	NM Flat Gk, EN 1514-1, RF as per EN 1092-1, PN 16, IBC Type, Thk-3.2mm, Klingsersil C-4430, TA-Luft & EC1935 (D.S. 5101) / CNAF,	C1NKU6DV	1
11	24	135 SBLT 2 HHx N&2W, ISO 261/ISO 4032, Full Length Threaded, F.Wash. EN ISO 887, A2, EN ISO 7089 ISO 3506-1 Gr.A2-70,	C3JHBD3	8
12	16	160 SBLT 2 HHx N&2W, ISO 261/ISO 4032, Full Length Threaded, F.Wash. EN ISO 887, A2, EN ISO 7089 ISO 3506-1 Gr.A2-70,	C3JHBD8B	24
13	16	100 SBLT 2 HHx N&2W, ISO 261/ISO 4032, Full Length Threaded, F.Wash. EN ISO 887, A2, EN ISO 7089 ISO 3506-1 Gr.A2-70,	C3JHBD7Z	8
14	100	But Waf, PN 16, RF or FF, Datasheet: 6102 / Ductile Iron, GENERIC TRANSMITTER SCREWED 021403PT012	C1UYHNWF	2
15	40	GENERIC TRANSMITTER SCREWED 021403PT012	- -	1

**PIPING DPT.**  
**SUPPORTED**  
By mfernandez1 at 3:41 pm, Jan 13, 2021

**PIPING DPT.**  
**SUPPORTS CHECKED**  
By Sergio Zamora at 4:13 pm, Jan 13, 2021

0	16/12/20	APN	LPD	OMC	IFC-ISSUED FOR CONSTRUCTION
REV	DATE	DWN	CHK	APP	DESCRIPTION

ALL dimensions to be checked in field prior to construction. Dimensions and routing shall be field adjusted, it is the piping contractors responsibility to check and verify all closing dimensions to equipment and make adjustments as required in field. All dimensions, elevations and coordinates are in millimeter unless noted otherwise. Fieldwelds and overlengths to be determined by piping contractor. Bolt holes to straddle horizontal and vertical centerline unless shown otherwise. Contractor will provide all necessary pipe supports.							
<b>PROJECT DESCRIPTION/LOCATION</b>							
BUTTERFLY PROJECT/KREFELD							
<b>TechnipFMC</b> <b>Cargill</b>							
<b>PROCESS UNIT</b>	<b>DESIGN AREA</b>	<b>LINE NUMBER</b>			<b>TRAIN</b>	<b>sheet</b>	<b>REV</b>
024	023A1	021403-100-WWG-16SS21-0005			01	1 OF 2	0



## MATERIAL LIST – FABRICATION

<u>PT NO</u>	<u>N.S. (MM)</u>	<u>DESCRIPTION</u>	<u>IDENT</u>	<u>QTY</u>
1	100	Pipes (Length), EN 10220, BE, EFW + 100% RT, - ,/2.6MM EN 10217-7 Gr.X2CrNi19-11,	C1KV25CN	21.6M
2	100 x 40	Half Coup, Prj Std, BSPPF End, 40 Bar, - , - ,/ EN 10216-5 Gr.X2CrNi19-11,	C3CLV94W	1
3	100	90° Elb LR, EN 10253-4 Type A, BW Ends, Welded + 100% RT, M.3D, Serie 2,/2.6MM EN 10253-4 Gr.X2CrNi19-11,	C1P0SBDW	8

MATERIAL LIST - ERECTION

<u>PT NO</u>	<u>N.S. (MM)</u>	<u>DESCRIPTION</u>	<u>IDENT</u>	<u>QTY</u>	
4	40	GENERIC TRANSMITTER,SCREWED	021403PT001	- -	1

**PIPING DPT.**  
**SUPPORTED**

By mfernandez1 at 3:41 pm, Jan 13, 2021


**PIPING DPT.**  
**SUPPORTS**  
**CHECKED**

By Sergio Zamora at 4:13 pm - Jan 13, 2021


0	16/12/20	APN	LPD	OMC	IFC-ISSUED FOR CONSTRUCTION
REV	DATE	DWN	CHK	APP	DESCRIPTION

All dimensions to be checked in field prior to construction. Dimensions and routing shall be field adjusted, it is the piping contractors responsibility to check and verify all closing dimensions to equipment and make adjustments as required in field. All dimensions, elevations and coordinates are in millimeter unless noted otherwise. Fieldwelds and overlengths to be determined by piping contractor. Bolt holes to straddle horizontal and vertical centerline unless shown otherwise. Contractor will provide all necessary pipe supports.

NOTES:		REFERENCES / DOCUMENTS		SPEC	16SS21	PROJECT DESCRIPTION/LOCATION		horizontal and vertical centerline unless shown otherwise. Contractor will provide all necessary pipe supports.						
				SYMBOLS		BUTTERFLY PROJECT/KREFELD								
For pipes < dn50 supporting to be studied and defined by construction contractor before line fabrication and installation.		LINE LIST	30201-042-001000-001	Insulated Pipe — — — — — — — — — — — —	Insulated and Traced Pipe — — — — — — — —	PROCESS UNIT		DESIGN AREA		LINE NUMBER		TRAIN	SHEET	REV
		ISOMETRIC INDEX	30303-042-023000-200											
		PIPING SUPPORT	30207-042-021300-001			024		023A1		021403-100-WWG-16SS21-0005		01	2 OF 2	0



**VOID**



# **VOID**

MATERIAL LIST - FABRICATION					
PT NO	N.S. (MM)	DESCRIPTION		IDENT	QTY
1	100	Pipes (Length), EN 10220, BE, EFW + 100% RT, -, /2.6MM EN 10217-7 Gr.X2CrNi19-11,		C1KV25CN	21.9M
2	100 x 40	Half Coup, Prj Std, BSPPF End, 40 Bar, -, -, / EN 10216-5 Gr.X2CrNi19-11,		C3CLV94W	1
3	100	90° Elb LR, EN 10253-4 Type A, BW Ends, Welded + 100% RT, M.3D, Serie 2,/2.6MM EN 10253-4 Gr.X2CrNi19-11,		C1P0SBDW	8

MATERIAL LIST - ERECTION					
PT NO	N.S. (MM)	DESCRIPTION		IDENT	QTY
4	40	GENERIC TRANSMITTER.SCREWED 021403PT001		--	1

PIPING DPT.  
**DESIGNED**

*By apereznune at 11:01 am, Dec 16, 2020*

PIPING DPT.  
**DESIGN CHECKED**

*By rvasquezhu at 11:20 am, Dec 16, 2020*

All dimensions to be checked in field prior to construction. Dimensions and routing shall be field adjusted, it is the piping contractors responsibility to check and verify all closing dimensions to equipment and make adjustments as required in field. All dimensions, elevations and coordinates are in millimeter unless noted otherwise. Fieldwelds and overlengths to be determined by piping contractor. Bolt holes to straddle horizontal and vertical centerline unless shown otherwise. Contractor will provide all necessary pipe supports.

NOTES:		REFERENCES / DOCUMENTS		SPEC	16SS21	PROJECT DESCRIPTION/LOCATION		horizontal and vertical centerline unless shown otherwise. Contractor will provide all necessary pipe supports.				
				SYMBOLS		BUTTERFLY PROJECT/KREFELD						
For pipes < dn50 supporting to be studied and defined by construction contractor before line fabrication and installation.		LINE LIST	30201-042-001000-001	Insulated Pipe — — — — — — — — — — — —	Insulated and Traced Pipe — — — — — — — —	PROCESS UNIT		DESIGN AREA	LINE NUMBER	TRAIN	SHEET	REV
		ISOMETRIC INDEX	30303-042-023000-200									
		PIPING SUPPORT	30207-042-021300-001			024		023A1	021403-100-WWG-16SS21-0005	01	2 OF 2	0